



To,

**All the Prequalified Contractors**

For the construction of the PSDP Funded Multi-Purpose Building of ITU

**Subject: ADDENDUM – 02 TO THE BIDDING DOCUMENTS FOR THE CONSTRUCTION OF PSDP FUNDED MULTI-PURPOSE BUILDING OF INFORMATION TECHNOLOGY UNIVERSITY OF THE PUNJAB AT BARKI ROAD, LAHORE**

1. Further, to clarifications requested by participant(s) of the bid for subject project, Addendum – 02 to the bidding documents is hereby issued with details appended below. The Addendum 1 and 2 shall be read and considered as part of the bidding document. The instructions provided in the addendums shall be followed and the bids must be submitted accordingly.

A	B	C	D	E	F	G
Division	Sr. No.	Current Description	Clarifications & Final Description, & Decision	Details	Total Qty. G/F & F/F	Sizes (ft)
4	4.3	Providing and fixing in position fixed aluminum windows & Ventilators using high strength aluminum alloy, extruded section 100mmx50mmx1.30mm thick of ALCO or approved equivalent, galvanized steel screws, 5mm thick clear glass made by "Ghani Glass" or approved equivalent without undulation and waves, with rubber gasket, best quality approved USA made matching wire gauze in openable area, standard hardware, brushes, aluminum section shall be anodized Champagne color and shock protected by lacquer film, as per drawings and specifications, complete in all respects and to the direction of the Engineer.	<p>1. The description of the item with respect to material (as reflected in the BOQs) shall remain the same.</p> <p>2. Window sizes have been updated as reflected in Column G, and quantity has been updated as reflected in Column F, and shall be followed. <b>The bid shall be submitted in per square feet rate instead of numbers.</b></p>	<p>W-1</p> <p>W-2</p> <p>W-3</p> <p>W-4</p> <p>W-5</p> <p>W-6</p>	<p>4</p> <p>2</p> <p>4</p> <p>2</p> <p>35</p> <p>8</p>	<p>20x9</p> <p>15x24</p> <p>12x9</p> <p>10x9</p> <p>8x9</p> <p>7x26.5</p>
5	5.1	Providing & fixing ASH Wood carved panel door with Ash wood chowkhat (Single/Double Leaf) with 8mm thick Glass design fine polished, as per drawing, Partially carved and partially Glazed as per pattern on drawing including Ash wood Architrave/Gola border, polishing, ironmongery and all fitting accessories as per instruction of engineer incharge best quality.	<p>1. The description of the item with respect to material has been revised and updated as below;</p> <p>2. Deodar/Ash-wood or equivalent (subject to approval of the Engineer) <b>flush doors</b> with wooden frame size 5 1/2" x 2 1/2" (with approved design of grooves) with hold-fasts embedded in adjoining surfaces, 1 3/4" thick single or double leaf flush shutters with solid core with 5 mm (minimum) thick commercial Ash wood laminated sheet hydraulically pressed on both sides with approved design of grooves, deodar wood architraves/ beads/ liping to shutters as shown on drawing or approved by the engineer including G.I sheet Double padam Doors frame 14 SWG in specified width of dully fixed in chowkat with heavy duty 4No. steel hinges, M.S Rowel bolt for Hold Fast G.I chowkat,</p>	SFT		

6<sup>th</sup> floor, Arfa Software Technology Park, 346-B, Ferozepur Road, Lahore

[www.itu.edu.pk](http://www.itu.edu.pk)

T : +92 42 99046003

E : [oew@itu.edu.pk](mailto:oew@itu.edu.pk)

pg 1/2



			all hardware, imported lock, tower bolt, push plate, kick plates, fitting, and painting/polishing complete in all respect. 3. The sizes of the doors shall remain the same as reflected in the BOQS, and bid shall be submitted in <b>per square feet</b> rate instead of numbers.	
6	6.3	Providing and fixing 3"x2"MS Louver of 16 gauge Including black Powder coated finish, Hardware as per drawing and complete in all Respect.	1. The description of the item with respect to material and sizes shall remain the same as reflected in the BOQS. 2. MS Louvers are mentioned in the BOQs whereas Aluminum is mentioned on the drawing It is hereby clarified that the component will be executed in MS. 3. The unit has already been changed from RFT to SFT as clarified in the previous email.	
6	6.4 G/f & 6.2 F/f	Cement Coat Weather Shield (External Paint) Providing and applying at any 3 coats of Cement Coat Weather shield "ICI", "DULUX", "MASTER" or approved equivalent on external Wall plaster area, including one primer coat after removing any unevenness by filling with approved quality of plaster of paris and zinc etc., complete in all respect and direction of Engineer.	Weather Shield is mentioned in the BOQs, whereas Rock Wall is mentioned on the drawing. It is hereby clarified that Weather Shield shall be followed.	
2	2.1,2.2,2.3 & 2.4		1. Base prices for the finishing items, i.e., porcelain tile for floor BOQ item no [1.1], shall be [RS.3000 per SQM] 2. Base prices for the finishing items, i.e., Turkish Imported tile for corridor BOQ item no [1.2], shall be to [RS.4500 per SQM] 3. Base prices for the finishing items, i.e., Ceramic tile for washroom floor & wall BOQ item no [1.3], shall be to [RS.3000 per SQM] 4. Base prices for the finishing items, i.e., Granite Marble BOQ item no [2.1], shall be to [RS.2000 per SFT]	
12 & 13	--		Missing units for item No 12 shall be (SFT), and for item No 13 shall be (CFT)	

2. Please contact us if you need any further information or clarifications.

CC:

1. PA to the Registrar, Information Technology University of the Punjab

6<sup>th</sup> floor, Arfa Software Technology Park, 346-B, Ferozepur Road, Lahore

[www.itu.edu.pk](http://www.itu.edu.pk)

**Project Director**  
Information Technology University of the Punjab

T : +92 42 99046003

E : oew@itu.edu.pk